


THE DESIGNS INDICATED IN THESE DRAWINGS ARE PROPERTY OF R+N Architecture. ALL COPYRIGHTS RESERVED © 2022



1 PROPOSED FLOOR PLAN

SCALE: 1/4" = 1'-0"

GENERAL NOTES

PRIOR TO CONSTRUCTION CONTRACTOR SHALL VERIFY CLEARANCES OF DUCTWORK AND LIGHTS. REPORT ANY DISCREPANCIES TO ARCHITECT PRIOR TO CONSTRUCTION.

INTERIOR WALL AND CEILING FINISHES COMPLYING WITH NFPA 101 CHAPTER 10.2.3 SHALL BE CLASS A OR CLASS B IN EXITS AND IN ENCLOSED CORRIDORS FURNISHING ACCESS TO EXITS; AND CLASS A, CLASS B, CLASS C IN OFFICE AREAS.

INTERIOR FLOOR FINISH COMPLYING WITH NFPA 101 CHAPTER 10.2.7 SHALL BE CLASS I OR CLASS II IN CORRIDORS AND EXITS.

THIS BUILDING IS PROTECTED BY SUPERVISED AUTOMATIC SPRINKLER SYSTEM. (CONTRACTOR TO PROVIDE ENGINEERED SHOP DRAWINGS PRIOR TO COMMENCEMENT OF CONSTRUCTION.

CONTRACTOR TO COORDINATE CABINET INSTALLATION WITH ELECTRICAL OUTLET LOCATIONS. REFER TO ELECTRICAL DRAWINGS AND CABINET SHOP DRAWINGS.

CONTRACTOR TO COORDINATE ALL INTERIOR BUILT-INS AND INTERIOR FINISHES - FLOORING, CEILINGS, PAINT, PLASTIC LAMINATING, ETC. - COLOR AND STYLE WITH TENANT/OWNER PRIOR TO FABRICATION AND/OR INSTALLATION.

PIPES AND WIRES PASSING THROUGH FIRE RATED PARTITION ASSEMBLIES ARE TO BE PROTECTED AS PER F.B.C. SECTIONS 705.5.1.2 AND 705.6.1.

ONE FIRE EXTINGUISHER MUST BE LOCATED PER 2500 SQ. FT. OF FLOOR SPACE WITH A MAXIMUM OF 75' FROM ANY ONE POINT IN THIS SPACE.

(1) FIRE EXTINGUISHERS REQUIRED (EXISTING)

FLAMMABLE AND COMBUSTIBLE MATERIALS, IF USED DURING CONSTRUCTION, SHALL BE HANDLED AND STORED IN ACCORDANCE WITH NFPA 30.

WALL LEGEND

	EXISTING WALL TO BE REMOVED
	PROJECTION OF SOFFIT OR HEADER ABOVE
	EXISTING STUD WALL TO REMAIN
	EXISTING 8" CMU WALL TO REMAIN
	NEW 8" 2 HRS FIRE RATED CMU WALL
	NEW FULL HEIGHT STUD WALL
	EXISTING 2 HR. FIRE RATED WALL TO REMAIN

REVISED SCOPE OF WORK:

ALL EXISTING EXTERIOR WALLS & DOORS ARE TO REMAIN UNALTERED, AND MAINTAIN THE EXISTING FIRE RATING.

EXISTING BUILDING PROTECTED BY AUTOMATED FIRE SPRINKLER SYSTEM THROUGHOUT.

FIRE DEPARTMENT NOTES:

1. ALL PERMITTED WORK TO COMPLY WITH FLORIDA FIRE PREVENTION CODE (FFPC) 7TH EDITION
2. ALL INTERIOR FINISHES SHALL COMPLY WITH (FFPC) 7TH EDITION NFPA 101 CHAPTER 10.2
3. ALL LIFE SAFETY SYSTEMS SHALL REMAIN ACTIVE AND FULLY OPERATION DURING CONSTRUCTION. NFPA 101 (2018 EDITION) CHAPTER 16
4. ALL DESIGNATED EGRESS SHALL REMAIN UNOBSTRUCTED THROUGHOUT THE DURATION OF THE PROJECT. NFPA 101 (2018 EDITION) CHAPTER 16.4

SCOPE OF WORK

- 1- INSTALL NEW CMU WALL AS INDICATED IN PLANS
- 2- REPAIR EXISTING CONCRETE SLAB FLOOR AND POLISH
- 3- REPAIR REMAINING GWB WALLS AT BATHROOMS AS NEEDED
- 4- NO WORK AT BATHROOMS, FREEZER & COOLER UNDER THIS PERMIT.

NOTES:

FIRE ALARM:

MODIFICATIONS TO THE EXISTING FIRE ALARM SYSTEM UNDER SEPARATE PERMIT. FIRE ALARM CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR CITY APPROVAL. FIRE ALARM CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH BUILDING MANAGEMENT ANY WORK RELATED TO THE EXISTING FIRE ALARM SYSTEM.

FIRE SPRINKLERS:

MODIFICATIONS TO THE EXISTING FIRE SPRINKLER SYSTEM UNDER SEPARATE PERMIT. FIRE SPRINKLER CONTRACTOR TO PROVIDE INSTALLATION DRAWINGS FOR FIRE DEPT APPROVAL

INTERIOR FINISHES:

ALL INTERIOR FINISHES TO COMPLY WITH COMBUSTIBILITY, FLAME SPREAD INDEX, SMOKE-DEVELOPED INDEX, FIRE RESISTANT RATING, STABILITY, APPLICATION AND ACOUSTICAL CRITERIA AS SET FORTH IN NFPA 101, 10.2.2, AND TABLE A.102.2.2 FOR AN EXISTING TYPE 1-A BUILDING, PROTECTED THROUGHOUT BY AN APPROVED, SUPERVISED, AUTOMATIC SPRINKLER SYSTEM IN ACCORDANCE WITH FFPC SECTION 9.7.1

FOR THIS BUILDING:

FOR EXIT - ACCESS CORRIDOR: CLASS A OR B FINISHES CLASSIFICATION
FOR ALL OTHER SPACES: CLASS A OR B FINISHES CLASSIFICATION


PROJECT: Interior Improvements Oak Ridge

4077 West Oak Ridge Road, Orlando, FL 32809

PROJECT OWNER:

Cram Holdings, LLC
2413 Enterprise Road
Orange County, FL 32835

ARCHITECT OF RECORD:




R+N Architecture

2500 N Military Trail, Suite 480, Boca Raton, FL 33431
Phone: 786.762.2679 C: 305.282.0005
Email: vh.rodriquez@rda-archint.com
www.rda-archint.com / AA26002510

MEP CONSULTANT:


STRUCTURAL CONSULTANT:

KEY PLAN



SIGNATURE / DATE / SEAL

NOT VALID IF MISSING SIGNATURE



Victor H. Rodriguez,
Registered Architect
State of Florida # AR0094965
305 . 282 . 0005 vh.rodriquez@rda-archint.com

BUILDING PERMIT

Issue (1) Issue Date / For 08.15.2022 / Permit Submittal

DDCI Project #: 2022-038

Drawn by: VHR

Approved by: VHR

SHEET INDEX

4 - Proposed Floor Plan - Legend - Notes
SCALE: 1/4" = 1'-0"

SHEET NO.

A1.02